]] **N3XTCON** 3D PRINT CATALOG

04 JAN 2024

CONTENT

01. INTRODUCTION.....

- 02. PRINTING METHODS.....
- 03. DESIGN GUIDELINES.....
- 04. PRINTING FINISHES.....
- 05. ON-SITE 3D PRINT.....
- 06. OFF-SITE 3D PRINT.....
- 07. PROCESS SUSTAINABILITY.....
- 08. THE MOCK UP.....

 007
 023
 029
 041
 047
 101
 209
 229



































INTRODUCTION

N3XTCON - NEXT GENERATION 3D-PRINTED CONCRETE STRUCTURES

N3XTCON is a project funded by Innovation Fund Denmark to develop a solution that brings 3D Concrete Printing to an industrial scale. As such, we move from the current experimental/exploration phase (i.e. small-scale demo projects without reinforcement) to a real productivity-increasing solution based on reinforced concrete.


The N3XTCON industrial solution paves the way for digital fabrication of the next generation of custom-made concrete structures that offers significant material savings and new architectural opportunities – all of it at lower costs when compared to traditional construction. Our development relies on current state-of-the-art knowledge on 3DCP and creates new knowledge on, 3DCP simulation based on material- and print parameters, upscaling of materials from mortar to concrete and novel reinforcement strategies for 3DCP.








With every technology comes a revolution - often where application lags behind potential.






3D printing in construction was first explored in the 2000s, and it is now that we're seeing feasible applications arrive...



Its advantages lie in reducing human labor while increasing precision and specificity.



1.0



222

110

1.1

In a market driven by economies of scale, where profit is only found in bulk...



...we are exploring a new modularity.

A bespoke kit of parts with the flexibility to adapt to any condition.






3D printing allows us to focus on the individual and tailor for the specific again...




...and it allows for structural and functional optimization that would otherwise be economically nonviable.

PRINTING METHODS





PRINTING SYSTEMS




SINGLE ROBOTIC ARM PRINTER GANTRY CRANE ROBOTIC PRINTER

3D PRINTING PROCESS

PRINTING METHODS

CONCRETE 3D PRINTING PROCESS


01 CONCRETE SUPPLY TO PRINTHEAD




CONCRETE 3D PRINTING PROCESS

02 DEPOSIT CONCRETE

03 PRINT OBJECT BY LAYERS






DESIGN GUIDELINES




DESIGN GUIDELINES



Typically, the maximum width for a layer is between 14mm and 40mm and the maximum layer height varies between 2mm and 12mm. It also varies based on different types of nozzles.

LAYER DIMENSIONS



The maximum cantilever is 2/3 of each layer based on the most advanced technology by Sika AG.

MAXIMUM ANGLE






In plan, it is easier to make curves and fillets rather than sharp corners due to the movement of the machine.








To be structurally stable and economically efficient, it is better to print a double wall instead of one thick wall. It saves material and the cavity space can be used for structure, insulation, piping, and perhaps even program.


LAYERS OF WALL



It is possible to consider the rotation of nozzle during the print. That could make the wall more structural, because each layer would adhere better to the layer below.

NOZZLE DIRECTION






Based on a 60 degree angle cantilever, the max radius to make the wall stable. Ro illorundis nust, untio consequodiam custi rest qui aborum est voluptati idempor ma sim conectempora pa ipsa qui suntur, non cus nobitae perchil ma vollest otatas ella

STABLE CURVED WALL









The dome works only in compression. The steeper the angle, the smaller the radius.

RADIUS = -ANGLE (X)



Due to the nature of the extrusion technique, it is technically not possible to print horizontal members without scaffolding or other considerations. Maximum cantilever is 1/3 of each layer which is about 60 degree angle.






At the beginning of each layer's extrusion, it is difficult to control the ejection and precision.

START OF PRINT






It is recommended to hide the starting point of the print or to integrate it within the structure.

START OF PRINT

DESIGN GUIDELINES


PRINTING FINISHES






NON-PLANAR PRINTING & VARYING LAYER HEIGHT

PATTERNS



LARGER PATTERNS



NON-UNIFORM TEXTURE

DIRECTION

PRINTING FINISHES TEXTURES AND PATTERNS

WALL CURVATURE



COLOR #1

COLOR #2

COLOR #3



COLOR #4

COLOR #5


PRINTING FINISHES COLOR AND GRADIENT

COLOR #6











MULTIPLE




MULTIPLE











BIG - ROW HOUSE OPTION A





DIRECTION

PROGRAM ZONING



WALL CURVATURE





SHELL

FLOOR PLAN









	UNIT A
FROUND FLOOI	R:
1ST FLOOR	
TOTAL:	







UNIT B

FROUND FLOOR: 1ST FLOOR TOTAL:

100M² 80M² 180M²



UNIT TYPOLOGY





UNIT C


FROUND FLOOR: 1ST FLOOR TOTAL:

48M² 73M² 121M²



AGGREGATION
















BIG - ROW HOUSE OPTION B





GLAZING

FAÇADE PLAY




BALCONY





CURVED WALLS


SHELL



UNIT


















Henning Larsen

Additive Manufacturing within three different areas





On site Typology Optimization & Modular systems



Row house Typology - Housing



Row house Studies Interior Section



Row house Studies Exterior





Staircase study Row house Typology



Staircase study Row house typology



Large Scale production Facility

ON-SITE PRINT

CHALLENGING THE CONVENTIONAL ROW HOUSE TYPOLOGY





Diagram & Plan & Axo - Explanatory Drawings

From conventional row house typology to a new one

Diagram & Plan & Axo - Explanatory Drawings












Diagram & Plan & Axo - Explanatory Drawings





Henning Larsen —

3D Printed Row Houses - Denmark




Diagram & Plan & Axo - Explanatory Drawings



Option 02



Option 03






Henning Larsen — Option 01

Option 03 - Back view



3D Printed Row Houses - Denmark / Studies








Large Scale Production Facility - Odense Havn Production Area









Henning Larsen —

3D Printed Row Houses - Denmark / Studies




Diagram & Plan & Axo - Explanatory Drawings





3D Printed Row Houses - Denmark / Studies





Diagram & Plan & Axo - Explanatory Drawings



3D Printed Row Houses - Denmark / Studies








Diagram & Plan & Axo - Explanatory Drawings

3D Printed Row Houses - Denmark / Studies




3DPrinted Row Houses - Denmark / Studies



Large Scale Production - Odense Havn

WHERE PRODUCTION FACILITIES MEET INOVATION AND 3D PRINTING



Large Scale Production Facility




Large Scale Production - Odense Havn

WHERE PRODUCTION FACILITIES MEET INOVATION AND 3D PRINTING



Large Scale Production - Odense Havn






Large Scale Production Facility - Odense Havn



Henning Larsen —

Large Scale Production Facility - Odense Havn Office Space



Henning Larsen —

Large Scale Production Facility - Odense Havn Production Area



Henning Larsen —

OFF-SITE PRINT



Concrete as a Material





Concrete is well known for its attributes of **strength**, **durability**, **resilience and safety**



Concrete can be hence poured into various formworks or shuttering configurations to form desired shapes and sizes.



Concrete Buildings' Lifespan is around **50-80 years**



The up-front cost to build with concrete is higher than that of wood or steel. However, concrete structures substantially benefit from **reduction in energy costs** over time.

CONCRETE



The amount of energy required for production of concrete is low compared with steel.




THERMAL MASSING Lower energy consumption



LOCAL AVAILABILITY Significant carbon savings in transportation.



DIFFUSION-OPEN Better Inner environment and **no plastic**



STEEL REDUCTION DESIGN Reduced use of raw materials and reduced waste

When taking the performance of a building over its whole lifecycle into account, concrete offers significant sustainability benefits over other building materials thanks to its innate properties, such as its durability, resilience, its thermal mass, its recyclability, its carbon uptake and its local availability.

CONCRETE AS A SUSTAINABLE MATERIAL



RECYLCING AND REUSING Reduced construction costs and environmentally friendly

Conventional Construction

Less efficiency and flexibility

3D Printing


PER

100







TRADITIONAL CONSTRUCTION



3D PRINTING



Constrained and non-flexible design



Flexibility Of Use

Decrease In Physical Labor

.



fill

06

ZIR BETC

IS BEAUGADINA 25 H. DEN FAZLA TRALADRA

STORES .

OFF-SITE PRINT TRADITIONAL CONSTRUCTION VS 3D PRINTING



OFF-SITE PRINT TRADITIONAL CONSTRUCTION VS 3D PRINTING

Reduced waste and material consumption for form work

 \bigcirc

200



Reuse



YE

109

OFF-SITE PRINT TRADITIONAL CONSTRUCTION VS 3D PRINTING

Flexibility of Use

A REAL







1131

OFF-SITE PRINT TRADITIONAL CONSTRUCTION VS 3D PRINTING





Prefabricated Elements



N3XTCON

N3XTCON



Modular Architecture

OFF-SITE PRINT






Increased Labor Efficiency Enables Personal Related **Costs to Decline**



Building and the Site Work Can Be Completed Simultaneously which makes it **Time efficient**



Less Framework **Decreased Material Waste**

Structures Modular



Factory Enviorement Prevents Any **Delays Caused By The Weather**



Easy and Fast to Construct and Deconstruct





PREFABRICATED ELEMENTS AND MODULAR CONSTRUCTION



Improved Construction Quality Due to Controlled Environment



Timber Frame Construction Causes **Limited Life Span**



Bespoke design process allows extreme flexibility in terms of space utilization, purpose of use and overall design.



3D printing the modules reduces the construction time and cost significantly.



The construction method is a more environmentally friendly as it encourages more green insulation materials and reduces the amount of plastic use.



3D PRINTED N3XTCON UNITS



Creating social sustainability that support societies through changing social needs by being enabling and physically flexible.




Henning Larsen


Additive Manufacturing within three different areas



HOUSING



PUBLIC/COMERCIAL



STRUCTURAL/ **ELEMENTS**



Off-Site Typology Optimization & Modular systems



Modular System - Upside down 3d printing




Optimized module 3d printed as a whole




Modular expression study 01




HOUSING



Typology Optimization - Various Scales



Typology Optimization - Various Scales/Elements



3D Printed modular Unit - Of site



PUBLIC

3d Printed Columns - Structural Optimization Common House

Modular expression study 02

Housing Project, Denmark

PROCESS EXPLANATION

This project will culminate in a prototype for a built structure showcasing the improved printing process developed during the partnership. Ultimately, our goal is to produce a full-scale 3D printing concrete building with reduced CO2 emissions.

The future impact of the N3XTCON project encompasses the highlighted UN Sustainable Development Goals.




Diagram the proccess of printing




Diagram & Plan & Axo - Explanatory Drawings





Diagram & Plan & Axo - Explanatory Drawings





Housing Project, Denmark

PROCESS EXPLANATION

The overall process aims to find ways to innovative while producing / 3D print modular units with all their optimal properties and assembling on site. One of the main benefits of additive manufacturing is that it allows architects and designers a great flexibility in design and creativity while being environmentally cautious while using less material. 3D printing these units of site in enclosed optimally controlled environments will substantially lower their environmental impact.










Modules interconnection technique















Henning Larsen —



Housing Project, Denmark








Modular System 3D Printed

Modular System 3D Printed

Ground Floor Plan

Modular System 3D Printed

Housing Project, Denmark







Henning Larsen —

OFF-SITE PRINT


Housing Project, Denmark



Ground Floor Plan









Second Floor Plan

Henning Larsen —







Housing Project, Denmark - Studies



Diagram & Plan & Axo - Explanatory Drawings

Diagram & Plan & Axo - Explanatory Drawings




Diagram & Plan & Axo - Explanatory Drawings



Diagram & Plan & Axo - Explanatory Drawings

Henning Larsen —









Henning Larsen —


OFF-SITE PRINT

Housing Project, Denmark






Housing Project, Denmark



Henning Larsen — **OPTIMIZE DEFINITION - PROOF OF CONCEPT**


optimize (v.) 1844, "to act as an optimist," back-formation from optimist. Meaning "to make the most of" is first recorded 1857. Related: Optimized; optimizing.



Henning Larsen —

Topology optimization – any object

Topology optimization – small scale






Present day: Topology optimization and/or 3d printing


The car industry



Topology optimization










Topology optimization








Henning Larsen —

70 % material savings with 4,5m cantilevers

OFF-SITE PRINT


Typology Optimization / Structural Elements



Typology Optimization of cores









CORE AND COLUMN STUDIES 02.

CORE AND COLUMN STUDIES 01.



CORE AND COLUMN STUDIES 03.



CORE AND COLUMN STUDIES 04.

OFF-SITE PRINT


Typology Optimization / Structural Elements



CORE AND COLUMN STUDIES



CORE AND COLUMN STUDIES



CORE AND COLUMN STUDIES



Henning Larsen —

Typology Optimization / Structural Elements



CORE AND COLUMN STUDIES

CORE AND COLUMN STUDIES




CORE AND COLUMN STUDIES Henning Larsen


CORE AND COLUMN STUDIES




Typology Optimization / Structural Elements



20 thick elements 3D printed with extra fine nozzle optimized to save material



40 mil thick elements 3D printed with fine nozzle Optimized to save material



One supportive roof-column element Optimized to save material


Typology Optimization / Structural Elements









BIG - PINEAPPLE








CONTINUOUS STRUCTURE

The Modular Elements Allows a Structure Easy To Construct and Deconstruct Which Creates a Reusable Structure.

The Modular Elements Alows To Create Continuous Shafts and Reduces or omits extra MEP inlaid Shafts

INSTALLATION AND STRUCTURE

CONTINUOUS SHAFTS



OFFICE

HOUSING

FLEXIBLE DESIGN







HOUSING

OFFICE

FLEXIBLE DESIGN






LINEAR


POINT

The Modularity of The Units Allows Diffrent Layouts and Flexibility On Site

FLEXIBLE DESIGN




COURTYARD



When it Comes to Transportation There is Some Off Site Constraints Like The Maximum Dimensions That we Can Build to Able to Transport is Important to Take in Considiration When Designing the Units to Reach the **Maximum Efficiency**

OFF SITE CONSTRAINTS





The Weight Of Each Unit is Also an Important Parameter When It Comes to Efficiency. Our Goal is to Reduce the Amount of Lifting and Transportation as Much as Possible to be More **Time and Cost Efficient** for Transporting the Units.

20 r

OFF SITE CONSTRAINTS








Each Unit Is Divided Into Two Pieces To Make The Transportation More Efficient

OFF SITE CONSTRAINTS





Taking in Consider The Constrains We are able to Transport **4 Units** at the Same Time Which Allows Us to Reduce the Time and Cost for the Transportation and Significant **Carbon Savings** In Transportation.


OFF SITE CONSTRAINTS




LIFECYCLE ANALYSIS STAGES





















OFF-SITE PRINT























OFF-SITE PRINT PROGRAM DISTRIBUTION









Mail Room 15 sqm

Shared Room 136 sqm Laundry Room Terrace Green House Kitchenette

OFF-SITE PRINT PROGRAM DISTRIBUTION







Bike Parking 177sqm 4 regular x 100 m2 **86 Spots** 1 cargo x 500 m2 **4 Spots**


500 m2 **4 Spots** 211sqm 1 Storage unit per apartment 1,5mx1m **64 Units**

Garbage Room 70sqm Adjacent to access road






OFF-SITE PRINT PROGRAM DISTRIBUTION



AREA m ²						FFFICIENCY		
FLOOR	UNIT	OUTDOOR	CIRCULATION	COMMON	COMMERCIAL	GFA	UNIT COUNT	EFFICIENCY
GF	82,94		52,79	15,28	153,09	304,1	3	17,36%
F01	233,48	24,78	70,71			328,97	9	23,25%
F02	233,48	24,78	70,71			328,97	9	23,25%
F03	233,48	24,78	70,71			328,97	9	23,25%
F04	233,48	24,78	70,71			328,97	9	23,25%
F05	233,48	24,78	70,71			328,97	9	23,25%
F06	233,48	24,78	70,71			328,97	9	23,25%
F07		167,74	24,62	136,6		328,96	0	15,27%
TOTAL	1483,82	316,42	501,67	151,88	153,09	2606,88	57	21,90%


BIKE PARKING	177,4 m²
DEPOT	211,5 m²
GARBAGE ROOM	70 m²
Total	458,9 m²



AREA m ²								
FLOOR	UNIT	OUTDOOR	CIRCULATION	COMMON	COMMERCIAL	GFA	UNIT COUNT	EFFICIENCY
GF	82,94		52,79	15,28	153,09	304,1	3	17,36%
F01	233,48	24,78	45,85			304,11	9	16,41%
F02	233,48	24,78	45,85			304,11	9	16,41%
F03	233,48	24,78	45,85			304,11	9	16,41%
F04	233,48	24,78	45,85			304,11	9	16,41%
F05	233,48	24,78	45,85			304,11	9	16,41%
F06	233,48	24,78	45,85			304,11	9	16,41%
F07		167,74	24,62	136,6		328,96	0	15,27%
TOTAL	1483,82	316,42	352,51	151,88	153,09	2457,72	57	16,46%

BIKE PARKING	177,4 m²
DEPOT	211,5 m²
GARBAGE ROOM	70 m²
Total	458,9 m²

OFF-SITE PRINT CORE STUDY - OPEN




STRUCTURAL 3D PRINTED CONCRETE WALL 100MM

EXTERIOR CONCRETE CLADDING 70MM

STAINLESS STEEL HANDRAIL

INTERIOR FLOOR FINISH **RADIANT FLOOR HEATING 70MM** ACOUSTICAL INSULATION 65MM STRUCTURAL 3D PRINTED CONCRETE SLAB 100MM



OFF-SITE PRINT UNIT EXPLODED AXO























II.















OFF-SITE PRINT MORE OPTIONS







PROCESS S SUSTAINABILITY





EMBEDDED CO₂ Low clinker and alternative binders Recycled materials





UNIT VOLUME Paste volume reduction

TOTAL VOLUME Structurally informed shapes Reduced waste Reusability

GLOBAL WARMING POTENTIAL (GWP) =



Х

DURABILITY Design for reuse

PARAMETERS THAT INFLUENCE THE GLOBAL WARMING POTENTIAL OF CONCRETE



A COMPARISON OF PRECAST CONCRETE AND 3D PRINTED CONCRETE



The Global Warming Potential of precast concrete



The Global Warming Potential of 3D printed concrete using a robotic arm




VS

At the precast concrete plant, the mixed concrete is poured into forms via bucket conveyors and concrete distributors. It is then heat treated for a few hours for better hardening and left for an additional 12 to 18 hours in a storage area for curing before the precast concrete elements are ready to be transported to the construction site (1).

PRECAST CONCRETE PROCESS

The Global Warming Potential of 3D printed concrete using a gantry



CONCRETE 3D PRINTING PROCESS




Table 1. Hourly Embodied Impacts of the case-study robotic Printing cells. These include the robotic arm, the

stirring/pumping/feeding device and the command system.

climate change	kg CO ₂ -Eq / hour	2,0E+00	1,8E+00
agricultural land occupation	m²*a / hour	4,4E-01	4,3E-01
Impact category	Unit	Hourly Embodied Impacts of the Printing Cell based on ABB 8700	Hourly Embodied Impacts of the Printing Cell based on ABB 8700

Table 3.	Hourly Operational Impacts of the case-study robotic Printing cells. These include the robotic arm, the	
	stirring/pumping/feeding device and the command system.	


Impact category	Unit	Hourly Operational Impacts of the Printing Cell based on ABB 8700	Hourly Operational Impacts of the Printing Cell based on ABB 6620
agricultural land occupation	m²*a / hour	6.20E-02	5.95E-02
climate change	kg CO2-Eq / hour	2.50E+00	2.40E+00

The operational impact is calculated based on data from PhD "Cement and concrete research: Environmental impact of extrusion-based additive manufacturing - generic model, power measurements and influence of printing resolution"(1). The research paper quantifies the climate change as GWP pr hour (see table 3 and 4). The data is representative for a robotic arm and uses an average of two robotic arm printers; the ABB 8700 and AB 6620 (2). The paper uses an estimated lifespan of 30.000 hours = 3,4 years for the 3D printing equipment. The paper also presents four settings for a robotic arm varying the printing speed and thickness (3).

This study uses the wall dimensions specified in BIG'S N3XTCON building design and the PhD data to compare the operational impact for printing 1 m³ of concrete.

DATA BACKGROUND FOR 3D PRINTING PROCESSES WITH ROBOTIC ARM





Printing fast uses more energy, but the robot has to run for a shorter period of time - resulting in the lowest carbon emissions!

GWP ACCORDING TO DIFFERENT PRINTING VELOCITIES





GWP OF PRECAST CONCRETE

Generic, C20/25, precast concrete representative for Europe (1)

291 kg CO2 eq / m3 concrete

GWP OF 3D PRINTED CONCRETE USING A ROBOTIC ARM

Generic C20/25, printed with 40 mm thickness and 200 mm/s (1)

264 kg CO2 eq / m3 concrete

Generic, C45/55, precast concrete representative for Europe (1)

354 kg CO2 eq / m3 concrete

Generic C45/55, printed with 40 mm thickness and 200 mm/s (1)

327 kg CO2 eq / m3 concrete

Given the same amount of reinforcement, the Global Warming Potential of precast concrete is compared to that of 3D printed concrete using a robotic arm.

VS

GWP OF PRECAST CONCRETE VS 3D PRINTED CONCRETE USING A ROBOTIC ARM


PROCESS S











SINGLE ROBOTIC ARM PRINTER

ROBOTIC PRINTER

We would like to compare the operational impact from the robotic arm with a gantry of the brand **COBOD**, since this one is likely to be used for N3XTCON!

COMPARISON OF ROBOTIC ARMS AND GANTRIES






4 types of insulation are being considered for the cavities inside the walls: light weight concrete, EPS, blown-in cellulose fibre insulation from recycled paper, and blown-in wood fibre insulation. A wall section is composed of two layers of 3D printed concrete, each 45 mm wide and a cavity of 90 mm for insulation

WALL BUILT UP FOR N3XTCON

WEIGHT

GLOBAL WARMING POTENTIAL



Rebars (3)

The aggregates weigh the most, but the cement is the biggest contributer to the GWP! Concrete with FutureCem has the lowest GWP.


COMPARING THE GWP OF DIFFERENT CONCRETE TYPES

Cement

Aggregates


THERMAL CONDUCTIVITY

GLOBAL WARMING POTENTIAL



A high thermal conductivity means low insulation quality.

COMPARING THE GWP OF DIFFERENT INSULATION TYPES



1,6 kg CO_2 eq / m² / year

3,4 kg CO₂ eq / m^2 / year*

* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and and the floor area is 31,8 m2 taking part of the shared hall way and stair case into account.

THE GWP OF ONE UNIT - USING MATERIALS WITH THE LOWEST CARBON FOOTPRINT


Triple glazing **0,7** kg CO₂ eq / m^2 / year

Window mullions made of pine wood

0,1 kg CO_2 eq / m² / year

Steel railings

0,1 kg $CO_2 eq / m^2 / year$



1,6 kg CO_2 eq / m² / year

6,5 kg CO2 eq / m² / year* **1** 90%

* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and and the floor area is 31,8 m2 taking part of the shared hall way and stair case into account.

THE GWP OF ONE UNIT - USING MATERIALS WITH THE HIGHEST CARBON FOOTPRINT


Window mullions made of aluminium

1,9 kg CO, eq / m² / year



Steel railings

0,1 kg $CO_2 eq / m^2 / year$



48510 kg CO₂ eq / floor plate* **3,4** kg CO_2 eq / m² / year

* This study is only considering the embodied energy of the N3XTCON precast project in concept stage. The analysis uses a reference life span of 50 years and and the floor area is 287 m2.

THE GWP OF ONE FLOOR PLATE - USING MATERIALS WITH THE LOWEST CARBON FOOTPRINT

PROCESS S

CONCRETE WALLS

REINFORCEMENT IN WALLS

INSULATION

Quantities for one unit 4.9 m³ concrete with FutureCem 2 Quantities for one unit 116 kg of steel

Quantities for one unit 8.9 m³ of insulation

Quantities for one floor plate 44 m³ concrete with FutureCem 2 Quantities for one floor plate 1043 kg of steel

Quantities for one floor plate 79 m³ of insulation

Assumptions

This study uses concrete with FutureCem 2 for the 3D printed walls. The ingredients ratio and specified aggregates are provided by the Danish Technological Institute (1). The footprint of one unit is 1,83 m2 and the height is 2,67 m. The concrete "pockets" around the reinforcement is assumed to be 200 mm x 300 mm.

Assumptions

The amount of reinforcement is based on the assumption of 2 rebars of 12 mm diameter C-C 1000 mm. Additional 8 mm horisontal rebar every 300 mm. 23,7 kg reinforcement / m³ concrete.

Assumptions

4 materials are being assessed for insulating The windows are triple glazing and two difthe 3D printed walls: Concrete with Futureferent materials are being compared for the mullions: pine and aluminium. Cem 1 (1), EPS (2), blown-in cellulose fibre insulation from recycled paper (3) and blown-in The mullions are assumed to have a linear wood fibre insulation (4). Fire retarandts EPS: weight of 2,14 kg/m for the pine wood and 3 hydrogen bromide, Cellulose: boric acid and kg /m for the aluminium mullions. borax, Wood fibre: nitrogen and phosphor The glazing consists of 3 glass panes each 4 and ammonium sulfate. Fire resistance class mm thick and with a 16 mm distance. for EPS. Cellulose and Wood fibre: Euroclass E.

Life cycle stages included A1-A3, A4, C3 and D

Life cycle stages included A1-A3. C4 and D

Life cycle stages included A1-A3. C4 and D

Reference life span 60 years

Reference life span 80 years

Reference life span 80 (EPS), 60 (concrete), 50 (cellulose fibre), 60 (wood fibre)

LIST OF MATERIAL SPECIFICATIONS AND QUANTITIES FOR THE LIFE CYCLE ANALYSES

WINDOW

Quantities for one unit

9 m² of glass and 16,2 m mullions

Quantities for one floor plate

81 m² of glass and 146 m mullions

Assumptions

Life cycle stages included

A1-A3, C3, C4 and D

Reference life span 20 (wood), 25 (glass)



SLAB

TOP FLOOR

PRECAST STAIRS AND ELEVATOR SHAFT

Quantities for one unit 31.8 m2 of concrete

Quantities for one unit 20 m2 of wood

Quantities for one unit 2,8 m3 of concrete, C45/55

Quantities for one floor plate 287 m2 of concrete

Quantities for one floor plate 180 m2 of wood

Quantities for one floor plate 25,4 m3 of concrete, C45/55

Assumptions

The slab is a precast concrete filigree slab and the reinforcement is assumed to be 150 kg steel / m³ of concrete (1). The slab is 80 mm thick.

Assumptions

The entire floor inside each unit is assumed to be covered with 20 mm planks of oak.

Assumptions

The central staircase and surrounding walls are included and the reinforcement is assumed to be 150 kg steel / m3 concrete for both stairs and elevator shaft.

Life cycle stages included A1-A3, C3 and D

Life cycle stages included A1-A3, C3 and D

Life cycle stages included A1-A3, C4 and D

Reference life span 75 years

Reference life span 60 years

Reference life span 60 years

LIST OF MATERIAL SPECIFICATIONS AND QUANTITIES FOR THE LIFE CYCLE ANALYSES

RAILINGS FOR THE BALCONY

Quantities for one unit 0,008 m3 of steel

Quantities for one floor plate 0,07 m3 of steel

Assumptions

The railings are made of steel and weigh 62 kg pr balcony.

> Life cycle stages included A1-A3, C4 and D

> > **Reference life span** 80 years



THE MOCK UP



















Danmarks Tekniske Universitet



DANISH TECHNOLOGICAL INSTITUTE



TESTING / ENGINEERING

3D PRINTERS

CONCRETE

INDUSTRY TRANSFORMATION

Henning Larsen —

ARCHITECTS